Specifications

Photo is representative

Eaton 197449

Eaton Moeller® series T0 T0, 20 A, surface mounting, 3 contact unit(s), 90 °, maintained, 0-1, in steel enclosure, Design number 15683

General specifications	
PRODUCT NAME	Eaton Moeller® series T0 On-off switch
CATALOG NUMBER	197449
EAN	4015080895862
PRODUCT LENGTH/DEPTH	200 mm
PRODUCT HEIGHT	127 mm
PRODUCT WIDTH	150 mm
PRODUCT WEIGHT	1.59 kg
CERTIFICATIONS	IEC/EN 60947-3 IEC/EN 60204 IEC/EN 60947 VDE 0660
MODEL CODE	T0-3-15683/SE1



Features & Functions	
FITTED WITH:	Black thumb grip and front plate
INSCRIPTION	0-1
NUMBER OF POLES	Three-pole

General	
DEGREE OF PROTECTION	NEMA 12
DEGREE OF PROTECTION (FRONT SIDE)	IP65
LIFESPAN, MECHANICAL	400,000 Operations
MOUNTING METHOD	Surface mounting
MOUNTING POSITION	As required
NUMBER OF CONTACT UNITS	3
OPERATING FREQUENCY	1200 Operations/h
OVERVOLTAGE CATEGORY	Ш
POLLUTION DEGREE	3
PRODUCT CATEGORY	On-Off switch
RATED IMPULSE WITHSTAND VOLTAGE (UIMP)	6000 V AC
SAFE ISOLATION	440 V AC, Between the contacts, According to EN 61140
SAFETY PARAMETER (EN ISO 13849-1)	B10d values as per EN ISO 13849-1, table C.1
SHOCK RESISTANCE	15 g, Mechanical, According to IEC/EN 60068-2-27, Half- sinusoidal shock 20 ms
SUITABLE FOR	Ground mounting
SWITCHING ANGLE	90 °

Climatic environmental conditions	
AMBIENT OPERATING TEMPERATURE (ENCLOSED) - MIN	-25 °C
AMBIENT OPERATING TEMPERATURE (ENCLOSED) - MAX	40 °C

Terminal capacities	
TERMINAL CAPACITY	2 x (0.75 - 2.5) mm ² , flexible with ferrules to DIN 46228 1 x (1 - 2.5) mm ² , solid or stranded 2 x (1 - 2.5) mm ² , solid or stranded 1 x (0.75 - 2.5) mm ² , flexible with ferrules to DIN 46228
SCREW SIZE	M3.5, Terminal screw
TIGHTENING TORQUE	8.8 lb-in, Screw terminals 1 Nm, Screw terminals

Electrical rating	
RATED BREAKING CAPACITY AT 220/230 V (COS PHI TO IEC 60947-3)	100 A
RATED BREAKING CAPACITY AT 400/415 V (COS PHI TO IEC 60947-3)	110 A
RATED BREAKING CAPACITY AT 500 V (COS PHI TO IEC 60947-3)	80 A
RATED BREAKING CAPACITY AT 660/690 V (COS PHI TO IEC 60947-3)	60 A
RATED OPERATIONAL CURRENT (IE) AT AC-21, 440 V	20 A
RATED OPERATIONAL CURRENT (IE) AT AC-23A, 230 V	13.3 A
RATED OPERATIONAL CURRENT (IE) AT AC-23A, 400 V, 415 V	13.3 A
RATED OPERATIONAL CURRENT (IE) AT AC-23A, 500 V	13.3 A
RATED OPERATIONAL CURRENT (IE) AT AC-23A, 690 V	7.6 A
RATED OPERATIONAL CURRENT (IE) AT AC-3, 220 V, 230 V, 240 V	11.5 A
RATED OPERATIONAL CURRENT (IE) AT AC-3, 380 V, 400 V, 415 V	11.5 A
RATED OPERATIONAL CURRENT (IE) AT AC-3, 500 V	9 A
RATED OPERATIONAL CURRENT (IE) AT AC-3, 660 V, 690 V	4.9 A
RATED OPERATIONAL CURRENT (IE) AT DC-1, LOAD-BREAK SWITCHES L/R = 1 MS	10 A
RATED OPERATIONAL CURRENT (IE) AT DC-13, CONTROL SWITCHES L/R = 50 MS	10 A
RATED OPERATIONAL CURRENT (IE) AT DC-21,	1 A

Short-circuit rating **RATED CONDITIONAL SHORT-CIRCUIT CURRENT** 6 kA (IQ) RATED SHORT-TIME 320 A, Contacts, 1 second WITHSTAND CURRENT 0.32 kA (ICW) **SHORT-CIRCUIT** 20 A gG/gL, Fuse, Contacts

PROTECTION RATING

240 V	
RATED OPERATIONAL CURRENT (IE) AT DC-23A, 120 V	5 A
RATED OPERATIONAL CURRENT (IE) AT DC-23A, 24 V	10 A
RATED OPERATIONAL CURRENT (IE) AT DC-23A, 240 V	5 A
RATED OPERATIONAL CURRENT (IE) AT DC-23A, 48 V	10 A
RATED OPERATIONAL CURRENT (IE) AT DC-23A, 60 V	10 A
RATED OPERATIONAL CURRENT (IE) STAR- DELTA AT AC-3, 220/230 V	20 A
RATED OPERATIONAL CURRENT (IE) STAR- DELTA AT AC-3, 380/400 V	20 A
RATED OPERATIONAL CURRENT (IE) STAR- DELTA AT AC-3, 500 V	15.6 A
RATED OPERATIONAL CURRENT (IE) STAR- DELTA AT AC-3, 690 V	8.5 A
RATED OPERATIONAL POWER AT AC-23A, 220/230 V, 50 HZ	3 kW
RATED OPERATIONAL POWER AT AC-23A, 400 V, 50 HZ	5.5 kW
RATED OPERATIONAL POWER AT AC-23A, 500 V, 50 HZ	7.5 kW
RATED OPERATIONAL POWER AT AC-23A, 690 V, 50 HZ	5.5 kW
RATED OPERATIONAL POWER AT AC-3, 380/400 V, 50 HZ	5.5 kW
RATED OPERATIONAL POWER AT AC-3, 415 V, 50 HZ	5.5 kW
RATED OPERATIONAL POWER AT AC-3, 690 V, 50 HZ	4 kW
RATED OPERATIONAL	5.5 kW

POWER STAR-DELTA AT 220/230 V, 50 HZ	
RATED OPERATIONAL	
POWER STAR-DELTA AT	7.5 kW
380/400 V, 50 HZ	
RATED OPERATIONAL	
POWER STAR-DELTA AT 500 V, 50 HZ	7.5 kW
RATED OPERATIONAL	
POWER STAR-DELTA AT	5.5 kW
690 V, 50 HZ	
RATED OPERATIONAL	
VOLTAGE (UE) AT AC - MAX	690 V
RATED UNINTERRUPTED CURRENT (IU)	20 A
UNINTERRUPTED	Rated uninterrupted
CURRENT	current lu is specified for
	max. cross-section.
UNINTERRUPTED	Rated uninterrupted
CURRENT	current lu is specified for max. cross-section.

Switching capacity	
NUMBER OF CONTACTS IN SERIES AT DC-21A, 240 V	1
NUMBER OF CONTACTS IN SERIES AT DC-23A, 24 V	1
NUMBER OF CONTACTS IN SERIES AT DC-23A, 48 V	2
NUMBER OF CONTACTS IN SERIES AT DC-23A, 60 V	3
NUMBER OF CONTACTS IN SERIES AT DC-23A, 120 V	3
NUMBER OF CONTACTS IN SERIES AT DC-23A, 240 V	5
RATED MAKING CAPACITY UP TO 690 V (COS PHI TO IEC/EN 60947-3)	130 A
VOLTAGE PER CONTACT PAIR IN SERIES	60 V
LOAD RATING	$1.3 \times I_e$ (with intermittent operation class 12, 60 % duty factor) $2 \times I_e$ (with intermittent operation class 12, 25 % duty factor) $1.6 \times I_e$ (with intermittent operation class 12, 40 % duty factor)

Contacts	
CONTROL CIRCUIT RELIABILITY	1 failure per 100,000 switching operations statistically determined, at 24 V DC, 10 mA)
NUMBER OF AUXILIARY CONTACTS (CHANGE- OVER CONTACTS)	0
NUMBER OF AUXILIARY CONTACTS (NORMALLY CLOSED CONTACTS)	1
NUMBER OF AUXILIARY CONTACTS (NORMALLY OPEN CONTACTS)	2

Actuator	
ACTUATOR COLOR	Black
ACTUATOR FUNCTION	Maintained
ACTUATOR TYPE	Short thumb-grip

Design verification	
10.2.2 CORROSION RESISTANCE	Meets the product standard's requirements.
10.2.3.1 VERIFICATION OF THERMAL STABILITY OF ENCLOSURES	Meets the product standard's requirements.
10.2.3.2 VERIFICATION OF RESISTANCE OF INSULATING MATERIALS TO NORMAL HEAT	Meets the product standard's requirements.
10.2.3.3 RESIST. OF INSUL. MAT. TO ABNORMAL HEAT/FIRE BY INTERNAL ELECT. EFFECTS	Meets the product standard's requirements.
10.2.4 RESISTANCE TO	UV resistance only in

ULTRA-VIOLET (UV) RADIATION	connection with protective shield.
10.2.5 LIFTING	Does not apply, since the entire switchgear needs to be evaluated.
10.2.6 MECHANICAL IMPACT	Does not apply, since the entire switchgear needs to be evaluated.
10.2.7 INSCRIPTIONS	Meets the product standard's requirements.
10.3 DEGREE OF PROTECTION OF ASSEMBLIES	Does not apply, since the entire switchgear needs to be evaluated.
10.4 CLEARANCES AND CREEPAGE DISTANCES	Meets the product standard's requirements.
10.5 PROTECTION AGAINST ELECTRIC SHOCK	Does not apply, since the entire switchgear needs to be evaluated.
10.6 INCORPORATION OF SWITCHING DEVICES AND COMPONENTS	Does not apply, since the entire switchgear needs to be evaluated.
10.7 INTERNAL ELECTRICAL CIRCUITS AND CONNECTIONS	Is the panel builder's responsibility.
10.8 CONNECTIONS FOR EXTERNAL CONDUCTORS	Is the panel builder's responsibility.
10.9.2 POWER- FREQUENCY ELECTRIC STRENGTH	ls the panel builder's responsibility.
10.9.3 IMPULSE WITHSTAND VOLTAGE	Is the panel builder's responsibility.
10.9.4 TESTING OF ENCLOSURES MADE OF INSULATING MATERIAL	ls the panel builder's responsibility.
10.10 TEMPERATURE RISE	The panel builder is responsible for the temperature rise calculation. Eaton will provide heat dissipation data for the devices.
10.11 SHORT-CIRCUIT RATING	Is the panel builder's responsibility. The specifications for the switchgear must be observed.
10.12 ELECTROMAGNETIC COMPATIBILITY	Is the panel builder's responsibility. The specifications for the switchgear must be observed.

10.13 MECHANICAL FUNCTION

The device meets the requirements, provided the information in the instruction leaflet (IL) is observed.

Resources	
CATALOGUES	P Switch-disconnectors and T Rotary cam switches catalogue CA042001EN
DECLARATIONS OF CONFORMITY	DA-DC-00004927.pdf
	DA-DC-00004895.pdf
DRAWINGS	eaton-rotary-switches-t0- main-switch-dimensions- 003.eps
	eaton-rotary-switches-t0- changeover-switch-3d- drawing.eps
	eaton-general-totally- insulated-t0-main-switch- symbol.eps
	eaton-general-rotary- switch-t0-step-switch- symbol.eps
	eaton-rotary-switches- front-plate-t0-on-off- switch-symbol-002.eps
ECAD MODEL	<u>DA-CE-ETN.T0-3-</u> 15683_SE1
INSTALLATION INSTRUCTIONS	<u>IL008054ZU</u>
WIRING DIAGRAMS	eaton-rotary-switches- switch-t0-main-switch- wiring-diagram-002.eps

PROJECT NAME:	
PROJECT NUMBER:	
PREPARED BY:	
DATE:	



Eaton Corporation plc

Eaton House 30 Pembroke Road Dublin 4, Ireland Eaton.com

© 2025 Eaton. All Rights Reserved.

Follow us on social media to get the latest product and support information.









