Specifications

Photo is representative

Eaton 199215

Eaton Moeller® series DILA Contactor relay, 110 V 50 Hz, 120 V 60 Hz, 2 N/O, 2 NC, Push in terminals, AC operation

General specifications	
PRODUCT NAME	Eaton Moeller® series DILA Control relay
CATALOG NUMBER	199215
MODEL CODE	DILA- 22(110V50HZ,120V60HZ)- PI
EAN	4015081972999
PRODUCT LENGTH/DEPTH	75 mm
PRODUCT HEIGHT	68 mm
PRODUCT WIDTH	45 mm
PRODUCT WEIGHT	0.227 kg
CERTIFICATIONS	IEC/EN 60947 VDE 0660 EN 60947-5-1 CSA File No.: 012528 CSA Class No.: 3211-03 UL File No.: E29184 UL 508 CSA-C22.2 No. 14-05 CE marking UL Category Control No.: NKCR UL CSA



Features & Functions	5
FEATURES	Positive operating contacts to EN 60947-5-1 appendix L, including auxiliary contact module
FITTED WITH:	Positive operation contacts

General	
APPLICATION	Contactor relays
DEGREE OF PROTECTION	IP20
SHOCK RESISTANCE	5 g, N/C auxiliary contact, Basic unit with auxiliary contact module, Mechanical, according to IEC/EN 60068-2-27, Half- sinusoidal shock 10 ms 7 g, N/O auxiliary contact, Basic unit with auxiliary contact module, Mechanical, according to IEC/EN 60068-2-27, Half- sinusoidal shock 10 ms
LIFESPAN, MECHANICAL	20,000,000 Operations (AC operated)
MOUNTING METHOD	DIN-rail/screw
CONNECTION	Push in terminals
OPERATING FREQUENCY	9000 Operations/h
OVERVOLTAGE CATEGORY	III
POLLUTION DEGREE	3
PRODUCT CATEGORY	DILA relays
PROTECTION	Finger and back-of-hand proof, Protection against direct contact when actuated from front (EN 50274)
RATED IMPULSE WITHSTAND VOLTAGE (UIMP)	6000 V AC
VOLTAGE TYPE	AC

Climatic environmental conditions	
AMBIENT OPERATING TEMPERATURE - MIN	-25 °C
AMBIENT OPERATING TEMPERATURE - MAX	60 °C
AMBIENT OPERATING TEMPERATURE (ENCLOSED) - MIN	-25 °C
AMBIENT OPERATING TEMPERATURE (ENCLOSED) - MAX	40 °C
AMBIENT STORAGE TEMPERATURE - MIN	-40 °C
AMBIENT STORAGE TEMPERATURE - MAX	80 °C
CLIMATIC PROOFING	Damp heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30

Terminal capacities	
TERMINAL CAPACITY (FLEXIBLE WITH FERRULE)	2 x (0.5 - 1.5) mm ² 1 x (0.5 - 2.5) mm ²
TERMINAL CAPACITY (SOLID)	1 x (0.5 - 2.5) mm ² 2 x (0.5 - 2.5) mm ²
TERMINAL CAPACITY (SOLID/STRANDED AWG)	20 - 14
STRIPPING LENGTH (MAIN CABLE)	10 mm
SCREWDRIVER SIZE	3.0 x 0.5 mm, Terminal screw

Electrical rating	
RATED OPERATIONAL CURRENT (IE)	10 A at 60 V, DC L/R ≤ 15 ms (with 2 contacts in series) 6 A at 110 V, DC L/R ≤ 15 ms (with 3 contacts in series) 6 A at 60 V, DC L/R ≤ 15 ms (with 1 contact in series) 10 A at 24 V, DC L/R ≤ 15 ms (with 1 contact in series) 3 A at 110 V, DC L/R ≤ 15 ms (with 1 contact in series) 4 A at 24 V, DC L/R ≤ 50 ms (with 3 contacts in series) 2 A at 110 V, DC L/R ≤ 50 ms (with 3 contacts in series) 1 A at 220 V, DC L/R ≤ 50 ms (with 3 contacts in series) 1 A at 220 V, DC L/R ≤ 50 ms (with 3 contacts in series) 5 A at 220 V, DC L/R ≤ 15 ms (with 1 contact in series) 5 A at 220 V, DC L/R ≤ 15 ms (with 3 contacts in series) 4 A at 60 V, DC L/R ≤ 50 ms (with 3 contacts in series) 4 A at 60 V, DC L/R ≤ 50 ms (with 3 contacts in series)
RATED OPERATIONAL CURRENT (IE) AT AC-15, 220 V, 230 V, 240 V	4 A
RATED OPERATIONAL CURRENT (IE) AT AC-15, 380 V, 400 V, 415 V	4 A
RATED OPERATIONAL CURRENT (IE) AT AC-15, 500 V	1.5 A
RATED INSULATION VOLTAGE (UI)	690 V
RATED OPERATIONAL VOLTAGE (UE) AT AC - MAX	690 V
SHORT-CIRCUIT PROTECTION RATING WITHOUT WELDING	10 A gG/gL, 500 V, Max. Fuse, Contacts
SAFE ISOLATION	400 V AC, Between auxiliary contacts, According to EN 61140 400 V AC, Between coil

Magnet system	
DUTY FACTOR	100 %
PICK-UP VOLTAGE	0.8 - 1.1 V AC x Uc (voltage tolerance - single-voltage coil 50 Hz and dual-voltage coil 50 Hz, 60 Hz)
POWER CONSUMPTION, PICK-UP, 50 HZ	24 VA, AC, Single- frequency coil 50 Hz and Dual-frequency coil 50/60 Hz
POWER CONSUMPTION, PICK-UP, 60 HZ	24 VA, AC, Single- frequency coil 50 Hz and Dual-frequency coil 50/60 Hz
POWER CONSUMPTION, SEALING, 50 HZ	3.4 VA, AC, Single- frequency coil 50 Hz and Dual-frequency coil 50/60 Hz 1.4 W, AC, Single- frequency coil 50 Hz and Dual-frequency coil 50/60 Hz
POWER CONSUMPTION, SEALING, 60 HZ	1.4 W, AC, Single- frequency coil 50 Hz and Dual-frequency coil 50/60 Hz
RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 50 HZ - MIN	110 V
RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 50 HZ - MAX	110 V
RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 60 HZ - MIN	120 V
RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 60 HZ - MAX	120 V
RATED CONTROL SUPPLY VOLTAGE (US) AT DC - MIN	0 V
RATED CONTROL SUPPLY VOLTAGE (US) AT DC - MAX	0 V
SWITCHING TIME (AC OPERATED, MAKE CONTACTS, CLOSING DELAY) - MIN	15 ms
SWITCHING TIME (AC OPERATED, MAKE	21 ms

	and auxiliary contacts, According to EN 61140
SWITCHING CAPACITY (AUXILIARY CONTACTS, GENERAL USE)	15 A, 600 V AC, (UL/CSA) 1 A, 250 V DC, (UL/CSA)
SWITCHING CAPACITY (AUXILIARY CONTACTS, PILOT DUTY)	A600, AC operated (UL/CSA) P300, DC operated (UL/CSA)

Communication	
CONNECTION TO SMARTWIRE-DT	No

CONTACTS, CLOSING DELAY) - MAX	
SWITCHING TIME (AC OPERATED, MAKE CONTACTS, OPENING DELAY) - MIN	9 ms
SWITCHING TIME (AC OPERATED, MAKE CONTACTS, OPENING DELAY) - MAX	18 ms

Contacts	
CODE NUMBER	22E
CONTROL CIRCUIT RELIABILITY	λ < 5 x 10-7 (1 failure at 2,000,000 operations for U_e = 24 V DC, Umin = 17 V, Imin = 5.4 mA) λ < 5 x 1/10 ⁷ (1 failure at 2,000,000 operations for U_e = 24 V DC, Umin = 17 V, Imin = 5.4 mA)
NUMBER OF AUXILIARY CONTACTS (CHANGE- OVER CONTACTS)	0
NUMBER OF CONTACTS (NORMALLY CLOSED CONTACTS)	2
NUMBER OF CONTACTS (NORMALLY OPEN CONTACTS)	2
NUMBER OF AUXILIARY CONTACTS (NORMALLY CLOSED CONTACTS)	2
NUMBER OF AUXILIARY CONTACTS (NORMALLY OPEN CONTACTS)	2

Design verification	
EQUIPMENT HEAT DISSIPATION, CURRENT- DEPENDENT PVID	0 W
HEAT DISSIPATION CAPACITY PDISS	0 W
10.2.2 CORROSION RESISTANCE	Meets the product standard's requirements.
10.2.3.1 VERIFICATION OF THERMAL STABILITY OF ENCLOSURES	Meets the product standard's requirements.
10.2.3.2 VERIFICATION OF RESISTANCE OF INSULATING MATERIALS TO NORMAL HEAT	Meets the product standard's requirements.
10.2.3.3 RESIST. OF INSUL. MAT. TO ABNORMAL HEAT/FIRE BY INTERNAL ELECT. EFFECTS	Meets the product standard's requirements.
10.2.4 RESISTANCE TO ULTRA-VIOLET (UV) RADIATION	Meets the product standard's requirements.
10.2.5 LIFTING	Does not apply, since the entire switchgear needs to be evaluated.
10.2.6 MECHANICAL IMPACT	Does not apply, since the entire switchgear needs to be evaluated.
10.2.7 INSCRIPTIONS	Meets the product standard's requirements.
10.3 DEGREE OF PROTECTION OF ASSEMBLIES	Does not apply, since the entire switchgear needs to be evaluated.
10.4 CLEARANCES AND CREEPAGE DISTANCES	Meets the product standard's requirements.
10.5 PROTECTION AGAINST ELECTRIC SHOCK	Does not apply, since the entire switchgear needs to be evaluated.
10.6 INCORPORATION OF SWITCHING DEVICES AND COMPONENTS	Does not apply, since the entire switchgear needs to be evaluated.
10.7 INTERNAL ELECTRICAL CIRCUITS AND CONNECTIONS	ls the panel builder's responsibility.
10.8 CONNECTIONS FOR EXTERNAL CONDUCTORS	ls the panel builder's responsibility.
10.9.2 POWER-	Is the panel builder's

Resources	
CATALOGUES	eaton-product-overview- for-machinery-catalogue- ca08103003zen-en-us.pdf
	Product Range Catalog Switching and protecting motors
DECLARATIONS OF CONFORMITY	DA-DC-00004789.pdf DA-DC-00004811.pdf
DRAWINGS	eaton-contactors- dimensions-007.eps
ECAD MODEL	ETN.199215.edz
INSTALLATION VIDEOS	WIN-WIN with push-in technology
MCAD MODEL	dil m7 15 pi.stp dil m7 15 pi.dwg
WIRING DIAGRAMS	2100SWI-108

STRENGTH	
10.9.3 IMPULSE WITHSTAND VOLTAGE	ls the panel builder's responsibility.
10.9.4 TESTING OF ENCLOSURES MADE OF INSULATING MATERIAL	Is the panel builder's responsibility.
10.10 TEMPERATURE RISE	The panel builder is responsible for the temperature rise calculation. Eaton will provide heat dissipation data for the devices.
10.11 SHORT-CIRCUIT RATING	Is the panel builder's responsibility. The specifications for the switchgear must be observed.
10.12 ELECTROMAGNETIC COMPATIBILITY	Is the panel builder's responsibility. The specifications for the switchgear must be observed.
10.13 MECHANICAL FUNCTION	The device meets the requirements, provided the information in the instruction leaflet (IL) is observed.

PROJECT NAME:	
PROJECT NUMBER:	
PREPARED BY:	
DATE:	



Eaton Corporation plc

Eaton House 30 Pembroke Road Dublin 4, Ireland Eaton.com

 $\hbox{@ 2025 Eaton.}$ All Rights Reserved.

Follow us on social media to get the latest product and support information.









