Specifications

Photo is representative

Eaton 276414

Eaton Moeller® series DILA Contactor relay, 24 V DC, 2 N/O, 2 NC, Screw terminals, DC operation

General specifications	
PRODUCT NAME	Eaton Moeller® series DILA Control relay
CATALOG NUMBER	276414
MODEL CODE	DILA-22(24VDC)
EAN	4015082764142
PRODUCT LENGTH/DEPTH	75 mm
PRODUCT HEIGHT	68 mm
PRODUCT WIDTH	45 mm
PRODUCT WEIGHT	0.294 kg
CERTIFICATIONS	IEC/EN 60947 IEC/EN 60947-4-1 UL Category Control No.: NKCR CSA Class No.: 3211-03 UL 508 CE UL UL File No.: E29184 CSA CSA-C22.2 No. 14-05 CSA File No.: 012528 EN 60947-5-1 VDE 0660



Features & Functions	
FEATURES	Positive operating contacts to EN 60947-5-1 appendix L, including auxiliary contact module
FITTED WITH:	Suppressor circuit Positive operation contacts Built-in suppressor circuit

General	
APPLICATION	Contactor relays
DEGREE OF PROTECTION	IP20
SHOCK RESISTANCE	5 g, N/C auxiliary contact, Basic unit with auxiliary contact module, Mechanical, according to IEC/EN 60068-2-27, Half- sinusoidal shock 10 ms 7 g, N/O auxiliary contact, Basic unit with auxiliary contact module, Mechanical, according to IEC/EN 60068-2-27, Half- sinusoidal shock 10 ms
LIFESPAN, MECHANICAL	20,000,000 Operations (DC operated)
MOUNTING METHOD	DIN-rail/screw
CONNECTION	Screw terminals
OPERATING FREQUENCY	9000 Operations/h
OVERVOLTAGE CATEGORY	Ш
POLLUTION DEGREE	3
PRODUCT CATEGORY	DILA relays
PROTECTION	Finger and back-of-hand proof, Protection against direct contact when actuated from front (EN 50274)
RATED IMPULSE WITHSTAND VOLTAGE (UIMP)	6000 V AC
VOLTAGE TYPE	DC

Climatic environmental conditions	
AMBIENT OPERATING TEMPERATURE - MIN	-25 °C
AMBIENT OPERATING TEMPERATURE - MAX	60 °C
AMBIENT OPERATING TEMPERATURE (ENCLOSED) - MIN	25 ℃
AMBIENT OPERATING TEMPERATURE (ENCLOSED) - MAX	40 °C
AMBIENT STORAGE TEMPERATURE - MIN	40 °C
AMBIENT STORAGE TEMPERATURE - MAX	80 °C
CLIMATIC PROOFING	Damp heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30

Terminal capacities	
TERMINAL CAPACITY (FLEXIBLE WITH FERRULE)	$2 \times (0.75 - 2.5) \text{ mm}^2$, Screw terminals $1 \times (0.75 - 2.5) \text{ mm}^2$, Screw terminals
TERMINAL CAPACITY (SOLID)	1 x (0.75 - 4) mm ² , Screw terminals 2 x (0.75 - 2.5) mm ² , Screw terminals
TERMINAL CAPACITY (SOLID/STRANDED AWG)	18 - 14, Screw terminals
STRIPPING LENGTH (MAIN CABLE)	10 mm
SCREW SIZE	M3.5, Terminal screw
SCREWDRIVER SIZE	0.8 x 5.5/1 x 6 mm, Terminal screw, Standard screwdriver 2, Terminal screw, Pozidriv screwdriver
TIGHTENING TORQUE	1.2 Nm, Screw terminals

Electrical rating	
RATED OPERATIONAL CURRENT (IE)	2 A at 110 V, DC L/R \leq 50 ms (with 3 contacts in series) 6 A at 110 V, DC L/R \leq 15 ms (with 3 contacts in series) 6 A at 60 V, DC L/R \leq 15 ms (with 1 contact in series) 3 A at 110 V, DC L/R \leq 15 ms (with 1 contact in series) 1 A at 220 V, DC L/R \leq 50 ms (with 3 contacts in series) 10 A at 24 V, DC L/R \leq 15 ms (with 1 contact in series) 10 A at 60 V, DC L/R \leq 15 ms (with 2 contacts in series) 5 A at 220 V, DC L/R \leq 15 ms (with 3 contacts in series) 1 A at 220 V, DC L/R \leq 15 ms (with 3 contacts in series) 4 A at 24 V, DC L/R \leq 50 ms (with 3 contacts in series) 4 A at 60 V, DC L/R \leq 50 ms (with 3 contacts in series) 4 A at 60 V, DC L/R \leq 50 ms (with 3 contacts in series)
RATED OPERATIONAL CURRENT (IE) AT AC-15, 220 V, 230 V, 240 V	4 A
RATED OPERATIONAL CURRENT (IE) AT AC-15, 380 V, 400 V, 415 V	4 A
RATED OPERATIONAL CURRENT (IE) AT AC-15, 500 V	1.5 A
RATED INSULATION VOLTAGE (UI)	690 V
RATED OPERATIONAL VOLTAGE (UE) AT AC - MAX	690 V
SHORT-CIRCUIT PROTECTION RATING WITHOUT WELDING	10 A gG/gL, 500 V, Max. Fuse, Contacts
SAFE ISOLATION	400 V AC, Between auxiliary contacts, According to EN 61140 400 V AC, Between coil

Magnet system	
DUTY FACTOR	100 %
PICK-UP VOLTAGE	0.7 - 1.3 V DC x Uc (at 24 V: without auxiliary contact module and at ambient air temperature + 40 °C) 0.8 - 1.1 V DC x Uc
POWER CONSUMPTION (PICK-UP) AT DC	2.6 W
POWER CONSUMPTION (SEALING) AT DC	2.6 W
RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 50 HZ - MIN	0 V
RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 50 HZ - MAX	0 V
RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 60 HZ - MIN	0 V
RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 60 HZ - MAX	0 V
RATED CONTROL SUPPLY VOLTAGE (US) AT DC - MIN	24 V
RATED CONTROL SUPPLY VOLTAGE (US) AT DC - MAX	24 V
SWITCHING TIME (DC OPERATED, MAKE CONTACTS, CLOSING DELAY) - MAX	31 ms
SWITCHING TIME (DC OPERATED, MAKE CONTACTS, OPENING DELAY) - MAX	12 ms
VOLTAGE TOLERANCE	Smoothed DC, three- phase bridge rectifiers or smoothed double-wave rectification

	and auxiliary contacts, According to EN 61140
SWITCHING CAPACITY (AUXILIARY CONTACTS, GENERAL USE)	15 A, 600 V AC, (UL/CSA) 1 A, 250 V DC, (UL/CSA)
SWITCHING CAPACITY (AUXILIARY CONTACTS, PILOT DUTY)	P300, DC operated (UL/CSA) A600, AC operated (UL/CSA)

Communication	
CONNECTION TO SMARTWIRE-DT	In conjunction with DIL- SWD SmartWire DT contactor module Yes

Contacts	
CODE NUMBER	22E
CONTROL CIRCUIT RELIABILITY	λ < 5 x 10-7 (1 failure at 2,000,000 operations for U _e = 24 V DC, Umin = 17 V, Imin = 5.4 mA)
NUMBER OF AUXILIARY CONTACTS (CHANGE- OVER CONTACTS)	0
NUMBER OF CONTACTS (NORMALLY CLOSED CONTACTS)	2
NUMBER OF CONTACTS (NORMALLY OPEN CONTACTS)	2
NUMBER OF AUXILIARY CONTACTS (NORMALLY CLOSED CONTACTS)	2
NUMBER OF AUXILIARY CONTACTS (NORMALLY OPEN CONTACTS)	2

0 W
0 W
1 W
15.5 A
3 W
Meets the product standard's requirements.
Does not apply, since the entire switchgear needs to be evaluated.
Does not apply, since the entire switchgear needs to be evaluated.
Meets the product standard's requirements.
Does not apply, since the entire switchgear needs to be evaluated.
Meets the product standard's requirements.

Resources	
CATALOGUES	Product Range Catalog Switching and protecting motors eaton-product-overview- for-machinery-catalogue- ca08103003zen-en-us.pdf
CHARACTERISTIC CURVE	eaton-contactors-dila-relay-characteristic-curve.eps eaton-contactors-component-dila-relay-characteristic-curve.eps
DECLARATIONS OF CONFORMITY	DA-DC-00004810.pdf DA-DC-00004792.pdf
DRAWINGS	eaton-contactors-module-dilm-dimensions.eps eaton-contactors-mounting-dilm-dimensions-002.eps eaton-contactors-mounting-dilm-dimensions.eps eaton-contactors-frame-dilm-dimensions.eps eaton-contactors-frame-dilm-dimensions.eps
ECAD MODEL	ETN.276414.edz
INSTALLATION INSTRUCTIONS	eaton-contactors-dila-dilm7-15-dilmp20-instruction-leaflet-il03407013z.pdf
INSTALLATION VIDEOS	WIN-WIN with push-in technology
MCAD MODEL	DA-CS-dil_m7_15
PED 500 240225	DA-CD-dil m7 15
PEP ECO-PASSPORT	EATO-00024-V01.01-EN
SYSTEM OVERVIEW	<u>eaton-contactors-dila-</u> <u>system-overview.eps</u>
WIRING DIAGRAMS	<u>2100SWI-109</u>

Does not apply, since the entire switchgear needs to be evaluated.
ls the panel builder's responsibility.
Is the panel builder's responsibility.
Is the panel builder's responsibility.
ls the panel builder's responsibility.
Is the panel builder's responsibility.
The panel builder is responsible for the temperature rise calculation. Eaton will provide heat dissipation data for the devices.
Is the panel builder's responsibility. The specifications for the switchgear must be observed.
Is the panel builder's responsibility. The specifications for the switchgear must be observed.
The device meets the requirements, provided the information in the instruction leaflet (IL) is observed.

PROJECT NAME:	
PROJECT NUMBER:	
PREPARED BY:	
DATE:	



Eaton Corporation plc

Eaton House 30 Pembroke Road Dublin 4, Ireland Eaton.com

© 2025 Eaton. All Rights Reserved.

Follow us on social media to get the latest product and support information.









